BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of Work :- Detailed Estimate for:- Annual maintenance and repairs of Street Lights in Ward No 3&4 Park Package Y-12 of Yelahanka Zone

Budget Head .....

Division No..... Estimate No. ..... For Rs.= **535451.10**

Sl No	SR Page No	Description of Work	Unit	Qty	Rate Per Year Rs. Ps.	Amount
1	AR Vide No SE (Ele) PR/676/2021-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below.i) Poles with 36/40 W fluorescent tube light street lighting system.	Each	1	685.45	685.45
2	AR Vide No SE (Ele) PR/676/2021-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 125 W HPMV light Park lighting system.	Each	710	756.29	536965.90
3	AR Vide No SE (Ele) PR/676/2021-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 250W HPSV light street lighting system.	Each	5	1019.41	5097.05
4	AR Vide No SE (Ele) PR/676/2021-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for with 400W HPSV street light/High Mast lighting systems.	Each	38	1118.08	42487.04
5	AR Vide No SE (Ele) PR/676/2021-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 70 watt HPMH park lighting systems.	Each	50	1013.085	50654.25

6	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 250 watt HPMH park lighting systems	Each	47	1123.14	52787.58
7	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents 400 watts HPMH street light/High Mast lighting systems.	Each	35	1214.22	42497.70
8	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB protective surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 24 watt LED streetlight lighting system	Each	179	880.01	157521.79
9	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB protective surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 65 watt LED streetlight lighting system	Each	6	1147.43	6884.58
10	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB protective surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 90 watt LED streetlight lighting system	Each	1	1377.66	1377.66
11	AR Vide No SE (Ele) PR/676/20 21-22, Dated: 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB protective surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 110/120 watt LED streetlight lighting system	Each	1	1575.5	1575.50
		Total Rs				898534.50

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

12	26/5.14.1	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts, necessary phase separators, handle and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) 100Amps 25kA.	Nos	10	4530.00	45300.00
13	40/6.4.4	Supplying of 1.1 KV LT UG cable XLPE or Heat resistant PVC insulated, PVC extruded Inner sheath armoured UG LT cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14 Ohms/Kms (Max) as per IS-3975 4 core 16 sqmm	Mtrs	400	150.00	60000.00
14	41/6.5.6	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.On wall /Structure 6 sqmm to 16 sqmm	Mtrs	400	30.00	12000.00
15	41/6.6.1	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary)	Mtrs	350	76.00	26600.00
16	30/ 5.42.2	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete.16SWG	Sqcms	180000	0.35	63000.00
17	26/ 5.13.4	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100 to 125Amps	Nos	13	7200	93600.00
18	32/ 5.48	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	13	4030.00	52390.00
19	27 5.17.3	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 50-63 Amps SP	Each	10	723.00	7230.00

(3)

20	66/ 12.7.2	Supply of LED pole mounting type post top lantern with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate/ clear glass material, delivering superior light output.Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB . LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in- house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 . Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED manufacturer & Cree/Nichia/ Lumileds/Osram make LED Source.LED Post Top Lantern with 35 watts	Nos ✓	10	6400.00 ✓	64000.00
		Work Portion Total (Rs)				424120.00
		GST 12% ITEM 12 to 20				50894.40
		Maintenance Portion				898534.50
		Misleniuos				535451.10
		Grand Total Rs				1909000.00

CERTIFICATE

1. The Place was inspected and work is essential
2. The Provision made in the estimate is adequate and are necessary.
3. The Work comes in the BBMP limit and is legitimate charges on the Corporation Funds.
4. The rates in the Estimate is based on KPWD Electrical SR 2019-20,BESCOM SR 2018-19 and approved rates
5. The Above work is not taken up in any previous Grants.

Asst. Engineer (Elec)

Asst. Exe.Engineer (Elec)
ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
Sub-Division No.
Bruhat Bangalore Mahanagara Palike
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

EXECUTIVE ENGINEER (ELEC)
ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
YELAHANKA DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Administrative Sanction for Rs. 1909000=00
Nineteen Lakh Nine thousand only
is accorded under PO300. M&K
for Street lights
Registered as EE No. 112/E.113 Subject
to conditions contained in enclosed memo
No. BBMP/Ele/EE/AS/22/2021-22
Dt

Technical Sanction for Rs. 19,09,000.00/-
(Rupees : Nineteen Lakh nine
thousand only.
is accorded under head PO300-M&
to street Lights SE/Ele/PR/709
Registered at SE (Ele) No.
to conditions contained in enclosed
No. 4/ Date: 9/12/2021
SE/Ele/TS/41/21-22

AE/AEE TA SE